

Waste to Energy Projects in Kansas

Frito-Lay, Inc. – Topeka Energy Center

David Knapp, P.E.
Sr. Project Manager



March 23, 2010

Performance with Purpose


- A vision for the future at Frito-Lay and PepsiCo
- Commitment to reduce environmental footprint from energy and water use
 - Zero Landfill
 - Compostable Bags
 - Membrane Bioreactor
 - Solar Energy
 - Landfill Gas
 - Biomass Boiler
 - Combined Heat & Power
 - High MPG Route Trucks
 - LEED Certification



Topeka Biomass Boiler

- Wood fuel fired
- Steam output ~ 60,000 #/hr (78.3 MMBTU/hr)
- Steam pressure ~ 410 psig
- Steam temperature ~ 450°F
- Efficiency ~ 70%
- Fuel as fired ~ 17,000 #/hr calculated
- Ash as fired ~ 520 #/hr calculated

Core Technology



Fuel Supply and Specification

Fuel Input ~ 360,000 MMBTU/year;
Fuel Supply ~ 35,000 tons/year;
Deliveries ~ 5/day

- Green wood (tree clippings, limbs, cuttings, chipped bark, chipped forest product waste)
 - 3900 to 4500 BTU/lb
 - 45 to 50% moisture (55% max)
- Dried chipped wood
 - 7000 to 9000 BTU/lb
 - 10% moisture
- Demolished building materials (pallets)
 - 4500 to 8000 BTU/lb
 - 12 to 40% moisture
- Tire derived fuel
 - 10,900 to 13,500 BTU/lb
 - Dry to 10% moisture
- Sawdust and sander dust
 - 8500 to 9000 BTU/lb
 - 5% moisture
- Pelletized grass and leaves
 - 5000 to 6500 BTU/lb
 - 10 to 20% moisture



Site Development September/October 2009



Equipment Deliveries December 2009



ESP Inlet



ESP Hopper



OFA Fan

Precipitator Installation December 2009



Boiler Foundation & Chain Wall December 2009



Site Progress

December 31, 2009



Boiler Tubing & Structural Steel January 2010



Tube Installation 1-15-10



Air Heater Structural Steel 2-1-10

Site Aerial Layout February 2010



Access Stairs & Platforms

February 2010



*West Catwalk Knee Brace
Installation 2-2-10*



Erecting the Stair Tower 2-4-10



*Dust Collector
Installation
Progress 2-3-10*



*Platform and Air
Heater Structural
Steel 2-3-10*

Progress Photos February 2010



Handrail Installation
2-8-10



Air Heater Fabrication
2-26-10



Air Heater Wall Assembly
2-12-10

Site Overview

March 1, 2010



Pipe Bridge Erection March 2010



Boiler Details

March 2010



*Air Heater
Tube
Installation
3-04-10*



*Rolled Tubes at Steam Drum
3-5-10*



*Bark Bin Structural
Steel 3-4-10*

East Header & Side Tubes

March 2010



West Side Tubes March 2010



Tube Installation 3-07-10



Tubes and Header 3-08-10

Fuel Conveyance

March 2010

Rail Spur



*Dust
Collector
Duct
Installation*



*30 Inch Belt
Conveyor*



*Fuel
Delivery
Chute
Installation*



Bark Bin, Flue Gas Duct & Tubing March 2010



Bark Bin Screws

Top of Bark Bin



*Primary & Secondary
Dust Collectors*



Side Wall Water Tubes



Top Steam Drum

- **Key Schedule and Deliverables**
 - Feasibility Study: Spring 2008
 - Project Definition: Fall 2008
 - Project Kickoff: March 2009
 - Design Completion: July 2009
 - Started Construction: October 2009
 - Startup & Commissioning: July 2010
 - Commercial Operation: August 2010
 - Performance Assessment: August 2010 – January 2012

Project Team

- Frito-Lay, Inc.
 - Topeka, KS Manufacturing Facility
- Burns & McDonnell Engineering, Inc.
 - Engineering, Architecture, Construction, Environmental & Consulting
- CPL Systems, Inc.
 - Leader in combustion control design and technology for over 15 years for biomass, landfill gas, bio-gas, multi-fuel boilers
- Alpha Boilers, Inc.
 - Over 30 years of experience with boilers ranging from 60,000 lbs/hr to 900,000 lbs/hr for the sugar, power, paper and wood industries
- PPC Industries
 - Pre-engineered factory built precipitators with gas flows to 30,000 ACFM
 - Dry electrostatic precipitator normally considered the best available control technology for wood fired boiler emissions



PPC INDUSTRIES
ELECTROSTATIC
PRECIPITATORS