KANSAS DEPARTMENT OF HEALTH & ENVIRONMENT BUREAU OF WATER (4/14/97) (Revised 12/03/97, Revised August, 2002, February 2007, January 2017, February 2020)

"INSTRUCTIONS FOR COMPLETING THE "WATER QUALITY PROTECTION PLAN"

KDHE is charged with protecting the waters of the state (K.A.R. 28-16-28). KDHE is also working to protect state water quality while minimizing interference in the construction/land alteration activities involving water resources and flood plains. KDHE encourages you to go through the thought process of how the project activity can create water quality impacts and the available measures to avoid or minimize water quality standard violations. The attached form will help you document your water quality protection measures (attach extra sheets if necessary). **This exercise could save you time and money by avoiding delays associated with investigations, litigation and lengthy processing procedures or investigating low cost alternatives.** Additionally, it may help reduce the potential for a registered public complaint, civil lawsuit, and save tax payers dollars, while protecting state water's beneficial uses for the citizens of Kansas and border states. Attachment 1 to these instructions, "CONSTRUCTION SITE POLLUTION CONTROL REFERENCE TOOL" and fact sheet, are good starting points for developing a water quality protection plan.

I. **Project information**: Fill in according to the NWP or 404 Application. Name, description, legal location, water body receiving discharge, owner/onsite contact.

II.&III. Activity: Refers to these possible project activities and associated water quality impacts.

Land clearing/dirt moving, fill, dredge, shaping- sediment, turbidity suspended solids, discharge of floating materials. Vegetation control/eradication using chemicals. Heavy equipment use- Spills of fuel, solvents, hazardous chemicals.

Vegetation Restoration- Potential Fertilizer application, storage, transport may result in nutrient enrichment (scum, excess mat algae, excess suspended algae (pea green) rooted vegetation).

Streambank Stabilization- Rip-rap using an unacceptable material such as asphalt, contaminated concrete rubble, creosote treated wood.

Construction waste- disposal according to state and local regulations and ordinances.

Removal of natural oxygen sources: riffles, rocks elevations in stream channel basin.

IV. Water Quality Protection Measures: Identify measures or practices to minimize water quality impacts.

Erosion/sediment control- Sediment ponds, filter strips, erosion control mats, silt fences, surface roughening, mulch etc.

Fertilizer- Apply fertilizer (phosphorus, nitrogen) according to label instructions in a manner that will not contribute to nutrients already in the waters.

Bank stabilization- Avoid using materials that may lose contaminants to ground and or surface water.

Spill Response- stop/slow leak if possible (clamp hose, plug hole etc.) Dial 911 and KDHE 785-291-3333 24 hours a day) have absorbents or spill kits on site, build a berm or temporary containment. *Spill Prevention plan*- assure all equipment is leak free before putting on site, keep mechanical fluids, containers and equipment an adequate distance from the waters edge. Implement vandalism minimization.

KANSAS DEPARTMENT OF HEALTH & ENVIRONMENT BUREAU OF WATER

WATER QUALITY PROTECTION PLAN

I. PROJECT INFORMATION Project Name: _____ Project Description: Project Legal Description and receiving water: II. Activity to Complete Project 3. <u>Potential Water Quality Impacts</u> (Use appropriate number from above). Sediment/ Erosion/ Suspended Solids Mechanical fluids/heavy metals Nutrients (nitrogen, phosphorus) Vegetation control/eradication chemicals

Low oxygen

WATER QUALITY PROTECTION PLAN

V. Water Quality Protection Measures for the	he above activities
. <u>. </u>	
•	
·	
··	
5	
have completed/ reviewed the Water Quali	ty Protection Plan and agree to ensure its implementation:
PROJECT OWNER:	DATE:
REPRESENTING:	DATE:
ITE PROJECT MANAGER:	DATE:
TOUT	

KDHE requests you to keep this plan on site during construction.

If the water body is considered by KDHE to be an OUTSTANDING NATIONAL RESOURCE WATER (ONRW), EXECPTIONAL STATE WATER (ESW) OR SPECIAL AQUATIC LIFE USE WATER (SALU), you should keep a copy of this plan on site during construction and submit a copy to:

Kansas Department of Health and Environment Bureau of Environmental Field Services Watershed Management Section 1000 SW Jackson St., Suite 430 Topeka, KS 66612-1367 (785) 296-4195 (785) 559-4258 CONSTRUCTION SITE POLLUTION CONTROL REFERENCE TOOL (See attached fact sheet for more water quality protection practices).

Water Quality Standard	Substances/actions Likely to	Water Quality Protection Practices
Criteria (From	Result in Violations of the	Water Quanty Protection Practices
K.A.R. 28-16-28 (e) et al.)	Water Quality Standards	
pH below 6.5	Acids, caustics,	Prevent or respond to equipment leaks or spills.
PH above 8.5	Tieras, caastres,	Report spill. Keep spill equipment (absorbents, socks
		etc.) on site. Push up berm etc. Locate and store
		substances an adequate distance from water resource.
		Implement vandalism prevention/ reduction
		practices.
Visible oil and grease	Fuel, mechanical maintenance	Prevent or respond to equipment leaks or spills.
	fluids, solvents, oil based	Report spill. Keep spill equipment (absorbents, socks
	paints.	etc.) on site. Push up berm etc. Locate and store
		substances an adequate distance from water resource.
		Implement vandalism prevention/ reduction
		practices.
Floating debris, solid	Artificial items, such as food	Good housekeeping, a portable waste container.
materials	containers, plastic paper or	Proper disposal of construction waste, rubbish,
	anything else which may	equipment parts, tires etc.
D: 1 1 50	trigger a complaint.	1 0 000
Dissolved oxygen below 5.0	Oxygen depletion from	Minimize stream geometry changes, removal of riffle
Biochemcial Oxygen	removal of natural aeration	and rocky areas. Design stream channel geometry for
Demand 3.0 mg/l (BOD)	sources or overloading organic	artificial sources of oxygenation.
Pesticides	matter. Substances which are used to	Follow Vancos Dagulations, follow label
resticides	control or eradicate living	Follow Kansas Regulations, follow label instructions, investigate mechanical / biological
	organisms (plants animals	alternatives.
	fungus).	anematives.
Suspended solids (sources)	Accelerated sedimentation,	Sediment/siltation: silt barriers/fences, sediment
	siltation and erosion form land	ponds, retention and detention dams, protect or
	disturbance, stream and bank	restore wetlands/riparian areas, establish buffer strip,
	alteration. If using heavy	stabilize streambank. Erosion: compaction, surface
	equipment see practices for	roughening, erosion control mats, mulch systems,
	hazardous, visible oil etc. and	vegetative plantings. Use mulch or hydro- seeding.
	pH criteria.	
Nutrients	Natural or commercial sources	Follow label instructions, apply according to
	of nitrogen, phosphorus.	vegetation needs rate. Use mulching techniques.
Toxics / hazardous	Any contaminant which affects	Prevent or respond to equipment leaks or spills.
	the health of a living, non-	Report spill. Keep spill equipment (absorbents, socks
	microbial organism. May	etc.) on site. Push up berm etc. Locate and store
	include infectious pathogens,	substances an adequate distance from water resource.
Chlorides	radioactive isotopes etc	Implement vandalism prevention /reduction practices
Sulfates		
	1	1

Notes for Water Watchers

Kansas Department of Health and Environment

November, 1994 (Revised October, 1997, Revised August, 2002, February 2007)

CONSTRUCTION SITE POLLUTION CONTROL

Loss of soil due to erosion is estimated to be 25.4 billion tons a year world wide. Improperly implemented activities which disturb land such as agricultural production, construction activities, or land clearing creates potential for sediment to be transported off the site, often affecting nearby water resources. When this off-site transport is accelerated or excessive, a serious pollution problem results. Degradation to the ecosystem results in increased public tax dollars which must be used for a) street cleaning and b) stormwater sewer maintenance, c) water treatment costs, d) flood repair and control, e) dredging or sediment removal from reservoirs. Excessive stream sediment also effects stream direction and flow, and may increase stream bank instability.

Adverse impacts include:

1) Reductions in: 2) Increases in: a) oxygen, a) temperature,

b) sunlight b) need for mechanical, biological and chemical pest control

c) growth c) chances for displacement of desirable or native species with

d) ability to secure food undesirable or non-native species.

e) satisfactory habitatf) suitable spawning beds

Additional pollution associated with construction sites concerns include chemical applications (nutrients and hazardous substances), hazardous and solid wastes, and fuel storage.

All construction activities need to be conducted in a manner that avoids or minimizes discharge to Kansas water resources. The following measures can be used to develop a construction site pollution control plan.

I. EROSION AND SEDIMENT CONTROL MEASURES

PLANNING PHASE

- * Disturb only what is needed for each phase of the project
- * Designate and use an equipment staging area
- * Write a pollution control plan for the project

TREATMENT AND APPLICATION

Rip-rap Geo-textiles Maintain and protect natural and buffer areas

Cover soil stock piles Temporary seeding Fiber Matting (with\without seed)

Hydro seeding Dust control Establish permanent vegetation (seeding and sodding)

Soil compaction Surface roughening Chemical Stabilization

ASSEMBLY REQUIRED

Stone outlet Gabions Hay bale barriers Stone check dams

Baffles/energy dissipators Grid pavers Level spreaders Silt screen

STRUCTURES

Earth dikes Retaining walls Diversions Terraces

Catchments Sediment traps Sediment control basin Sub-surface drains Gravel and stone filter berm Pollution containment wetlands Temporary swales

* Pollution control measures previously described work best when in combinations and when they are monitored and maintained to ensure their effectiveness.

II. CHEMICAL CONTROL/MANAGEMENT MEASURES

- 1. Limit application and amount (use only where problem exists), avoid migration of toxic substances (apply properly, and follow product label directions).
- 2. Ensure the proper storage and disposal of toxic substances.
- 3. Apply nutrients at rates necessary to establish and maintain vegetation without causing significant nutrient runoff to surface waters.

III. SOLID WASTE MANAGEMENT MEASURES

- 1. Temporarily locate a container (on-site) to hold solid waste containers and their remaining contents for permanent proper disposal (landfill or hazardous waste collection site).
- 2. When needed, dispose of solid waste in accordance with city, county and state regulations.

IV. FUEL STORAGE

- 1. Apply recommended pollution control measures
 - a) Locate storage area away from streams or lakes; avoid burying tanks
 - b) Paint the unit bright colors to reduce chances for collision
 - c) Develop a spill response plan (to whom and how to report a fuel spill)
 - e) Construct a temporary berm or install an artificial containment device
 - f) Contact your KDHE District Office for more information.

(Partial information above extracted from U.S. Environmental Protection Agency, Guidance Specifying Management Measures for Sources of Nonpoint Pollution in Coastal Waters, 1993.)

POLLUTION CONTROL PLAN REQUIREMENT AND TECHNICAL ASSISTANCE

- 1. Construction activities disturbing 1 or more acres need to secure a permit from KDHE BUREAU OF WATER- INDUSTRIAL PROGRAMS- (785) 296-5549.
- 2. Construction activities less than 1 acre do not need a permit, yet must avoid causing water pollution problems. Contact the local County Conservation District to inquire about a local plan which provides local guidance or contact the KDHE Watershed Management Section at (785) 296-4195.

 $Publication\ costs\ are\ financed\ in\ part\ through\ EPA\ Section\ 319\ Nonpoint\ Source\ Pollution\ Control\ Grant\ \#C9007405-01-0.$